Project no. 340-047

The CO₂ neutral workplace

Project manager: FAKTOR 3 ApS - Barbara Bentzen - Tel.: +45 8820 0220

Via light measurements, indoor environment PV cell effect measurements, development of control electronics in actuaries and PV cells and, based on a preliminary market analysis, the preliminary project prepared development of a $\rm CO_2$ neutral adjustable height table prototype. The prototype will be completed in Elforsk project 341-009 on the $\rm CO_2$ neutral workplace, aimed at developing a general concept in which indoor PV cells generate electricity for office equipment. The preliminary project selected three PV cell types as most promising for the main project: SunPower, Kyosemi and Risø-DTU's polymer PV cell, developed in Denmark.



